MYSORE PUBLIC WORKS DEPARTMENT.

HEADQUARTER RANGE, BANGALORE.

Dated the 18th August 1932.

Notice is hereby given that sealed tenders will be received at the Office of the Assistant Engineer, Headquarter Range, Bangalore, up to 10th September 1932 (2 P.M.) for constructing Parvathi Chandrasekhara Out-Patient Block to the New Maternity Hospital, Fort, Bangalore.

An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of November 1933.

2. The plans, detailed estimate and conditions may be seen at the Assistant Engineer's Office, Headquarter Range, Bangalore, between the hours of 11 A.M. and 5 P.M. on all working days.

3. Tenders should be submitted on printed forms which may be obtained from the Assistant Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed both in words and figures.

4. Each tender must be accompanied by a deposit of rupees two thousand (Rs. 2,000) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for the Construction of Parvathi Chandrasekhara Out-Patient Block attached to the New Maternity Hospital, Bangalore" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer of Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Assistant Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimate amount will not be accepted.

10. No claims for enhanced rates will be entertained on any account after acceptance of tenders.

11. The contractor will be dealt with in terms of the bond for any short progress or delay. In matters of all disputes about rates, measurements, quality of work, etc., and in all disputes of any kind the decision of the Chief Engineer will be final and legally binding on the contractors.

Abstract of estimate of quantities for tender for construction of Out-Patient Dispensary (Parvathi Chandrasekhara Out Patient Block) to the New Maternity Hospital at Bangalore.

Sl. No.	Items of Work	Unit	Quantity
1	Earth work excavation foundation and filling in basement including consolidation.	C.yd.	1,682
2	Filling in foundation with burnt granite stone gelly concrete in lime mortar in 4" layer with consolidation.	C.ft.	12,173
2a	Filling in foundations with old stones (from fort area within a readius of 3 furlongs) and sand in courses.	100 C.ft.	
3	Burnt size stone in lime mortar including bond stones 6' apart in foundation and basement.	,,	27,667
3a	Stone in lime mortar for above, using old stones from fort area as noted in (2 a) or ramp in front of Tippu Sultan's Palace.	C.ft.	
4	Burnt size stone in lime mortar with through bond stones 6' apart with clean neat joints and with 1" dressing for all quoins.	,,	13,081
5	Burnt stone slabs 6" thick dressed and fixed ...	S.ft.	3,138
6	Cement pointing stone masonry walls including scraping joints ½" to 1" deep.	Sq.	142·36

Sl. No.	Items of Work	Unit	Quantity
7	Reinforced brick work screens 4½" thick and necessary arrangements to fix door shutters lime mortar plastering and whitewashing complete.	S.ft.	423
8	Cut stone in lime mortar square pillars, with 6" to 8" courses as may be ordered, 12 ft. high, 18" at bottom and 15" at top; or circular R. C. columns with moulded caps and bases, 12 ft. high 18" diam. at battom and 15" at top.	C.ft.	478
9	Rolled steel beams and joists of approved make including lifting, hosting, and with a prime coat of approved paint and with necessary clamps, etc., complete.	Cwt.	395
10	Roofing with jackarch terrace as per specifications ...	Sq.	71·68
11	Flooring 3" to 4" granite slabs 2' square dressed and laid diagonally over 3" concrete bed and neatly cement pointing, etc., complete.	,,	33·98
11a	Flooring with cuddapah slabs 1½" to 2" thick complete as above.		
12	Flooring with 8" square cement tiles of approved colour on 3" lime mortar concrete bed neatly pointed with cement.	,,	24·04
13	Boxing girders with cement concrete for lintels including boring holes in girders check block, pipes, bolts and nuts and plastering with cement including chamfering, etc., complete.	C.ft.	62
14	Stone block cornice in two courses for front verandah 12" deep and 10" projections as per design including cement pointing, etc., complete.	Rft.	265
15	Stone block cornice in two courses 12" deep and 8" projection as per design including cement pointing, etc., complete.	,,	144
16	Plain parapet wall 2' high of burnt stone in lime mortar, with 2' width 6" blocking course containing deep holes 6" by 2" and 8" apart and 1½' thick of parapet wall with coping, etc., and pointing with cement, etc., on approved sketch.	,,	292
17	Parapet wall 2½' high cement concrete balusters 15" high.	,,	92
18	Teak wood windows with ventilators with frames 6" x 2" Iron fittings and frames fixed with bolts flush with wall and including silicate painting of approved colour window to be of approved sample.	S.ft.	574
19	Teak wood doors with ventilators frames 6" x 2½" panel shutters 1½" thick with iron fittings include silicate painting of approved colour the doors to be of approved sample.	,,	494

B. NARASIMHA IYENGAR,
Assistant Engineer.